BRUHAT BANGALORE MAHANAGARA PALIKE

SCHEDULE - B

Name of the work: Patching pot holes in main and cross roads of Sahakaranagara B,C and D Block, Defence colony, CQAL layout and surrounding area in ward no. 08.

Sl. No.	Approved Qty.	Description	Unit	Schedule-B Rates	
				B.B. Umesh	
				In Figures	In Words
1	305.06	Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work	cum	83.16	Rupees Eighty Three and Sixteen Paise Only
2	152.51	KSRRB M400-17: Providing, laying spreading and compacting graded stones aggregate to **wet mix macadam** specifications including premixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying, in uniform layers with paver in sub base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per MORTH specification NO. 406, **Page No. 157/ Item No. 20.18 / PWD SR 2015-16**	cum	1713.96	Rupees One Thousand Seven Hundred Thirteen and Ninety Six Paise Only
3	853.65	KSRRB 3000: **Filling Pot-holes and patch repairs with bituminous concrete, 40 mm,** KSRRB M3000-5, Removal of all failed material, trimming of completed excavation to provide firm vertical faces, cleaning of surface, painting of tack coat on the sides and base of excavation as per clause 500.3 back filling the pot hole with bituminous material as per clause 500.4 compacting, trimming and finishing the surface to form a smooth continuous surface, all as per clause 3004.2 complete as per specifications, MORTH specification No. 3004.2, **No. 250 / Item No. 35.5 PWD SR 2015-16**	Sqm	305.64	Rupees Three Hundred Five and Sixty Four Paise Only
4	419.00	Lead and disposal of item no. 1 & Road side debris	cum	110.24	Rupees One Hundred Ten and Twenty Four Paise Only

B.B.

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92